KADUR DIVISION.

Notification, dated 22nd August 1934.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 1 P.M. on 26th September 1934 for the work of maintenance to Thangli Tank, Register No. 1049 of Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees One hundred and twenty-five (125) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the work of maintenance to Thangli Tank Register No. 1049 of Kadur Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for maintenance work to Thangli Tank Register No. 1049 of Kadur Taluk.

Serial No.	Particulars	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earth picking top of bund for seat of new earth, work	S.yd.	0 0 1½	8,360	65
2	Earth work to bund with watering and tamping inc uding 20 feet lift and one furlong lead..	C.yd.	0 5 0	1,364	426
3	Gravelling top of bund, as per above deduction with two miles lead	C.yd.	1 5 3	1,393	1,850
	Total ..				2,341

L. A. H. WINCKLER,
Executive Engineer.

MEDICAL DEPARTMENT

OFFICE OF THE SENIOR SURGEON IN MYSORE, BANGALORE.

Memorandum No. C. 295-5, *dated 27th August* 1934.

The name of Midwife Dhanamanie Rajoo attached to the District Hospital, Tumkur (Female Department) is, at her own request, changed to "Mrs. Dhanamanie Titus."

S. SUBBA RAO,
Senior Surgeon.